



Engineering & Public Works
416 West Broadway Ave. Maryville, TN 37801
(865) 273-3500 | www.maryvillegov.com

Addendum #1

Bid No. 05-24

Fire Station 2 Parking Lot Reconstruction

Addendum Date: April 23, 2024

Owner: City of Maryville

Bid Opening Date: April 30, 2024

Total Pages: 1

The following addendum was issued to answer questions asked about the project (Total addenda issued: 1 of 1).

1. Can the entire work area be closed while demolition and concrete/asphalt take place?

Yes. Work shall commence after school is out for the summer, so the area under construction can be closed while work takes place. Firemen will be asked to park elsewhere, and any John Sevier Elementary School traffic will be expected to use the other entrance and parking lot. Note, Sequoyah Avenue should not be fully closed during construction.

2. In regard to elevations of the proposed asphalt and concrete, are we to remove 12" of existing material to put the elevations in relatively the same place?

Final elevations are to match those of existing elevations. To accommodate the proposed paving schedules, 12" of existing material is expected to be removed.

3. Can a mobilization item be added to the bid form?

Mobilization cost is to be factored into other bid items.

4. Does the "Mineral Aggregate, Type A Base, Grading D" item include the stone for the asphalt and concrete sections? Just making sure that we do not need to include the stone for the concrete in that bid item.

The quantity estimation for "Mineral Aggregate, Type A Base, Grading D" includes stone to be used for the entire reconstructed area, both asphalt and concrete sections.

End of Addendum No. 1